BRUHATH BANGALORE MAHANAGARA PALIKE,
Executive Engineer,Project Division,Rajarajeshwarinagar Zone
MODIFIED SCHEDULE - II

Name of Work :- CONSTRUCTION OF MPED BUILDING (GOVT SCHOOL) AT JALAHALLI VILLAGE IN WARD NO.16

Sl No	Description of Item	Unit	Qty	Rate in	
				Figures	Words
	2	3	4	5	6
1	Clearing grubbing road lane including up rooting rank vegitation , grass , bush , shrubs , sapling & trees of girth up to 300mm by manual means, in area of light jungle , removal of stumps , disposal of un serviceabale materials , stacking of serviceabale materials with in a lead of 100 mtr from road boundary , labour charges complete as per specifications	Sqm	700.00	7.00	Rupees Seven Only
2	Dismantling of Exsisting structures like Culverts, Bridges, retaining wall & other structures compraising of masonry, cement concrete, wood work, steel work including T& P and scaffolding wherever necessary, sorting the Dismentalled metrial,disposoble of unserviceble material & stacking servicable material with lead of 1000 mts, complete as per specification I.) Lime concrete/ Cement Concrete KSRRH M200 13.1 - do- II by mechanicaal means A cement Concrete Grade M 15- M20	Cum	84.75	428.00	Rupees Four Hundred Twenty Eight Only
3	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications.KSRRH M200 14.2. -do- Dismantling brick/Tile work B. In cement mortar. MORTH Specification No. 202	Cum	16.96	303.00	Rupees Three Hundred Three Only
	Above 125%	Cum	121.04	435.75	Rupees Four Hundred Thirty Five and Seventy Five Paise Only
4	Dismanteling of Exsisting structures like Culverts, Bridges, retaining wall & other structures compraising of masonry, cement concrete, wood work, steel work including T& P and scaffolding wherever necessary, sorting the Dismentalled metrial,disposoble of unserviceble material & stacking servicable material with lead of 1000 mts, III.3 complete as per specification III) Dismanteling of Stone masonary MORTH Specification 202	Cum	97.50	303.00	Rupees Three Hundred Three Only
5	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width in IN ORDINARY SOIL not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking of clods complete as per specifications.	Cum	551.90	235.00	Rupees Two Hundred Thirty Five Only
6	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width in IN HARD SOIL not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking of clods complete as per specifications.	Cum	157.70	351.00	Rupees Three Hundred Fifty One Only
7	KSRH 2.2.3 : Excavation by manual means for foundation of buildings, water supply & sanitary lines and electrical conduits etc., either in pits or in trenches 1.50m and above in width, in soft rock not exceeding 1.50mtrs in depth including stacking the excavated stuff clear from edges of excavation with lead upto 50mt including cost of explosives, labour, HOM of equipment complete as per specifications.	Cum	55.20	628.00	Rupees Six Hundred Twenty Eight Only

Executive Engineer

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
8	Earth work for lowering & levelling the ground other than foundation works by Mechanical means upto 3.0 mt depth including providing shoring stutting and bracing , removal of stumps and other and other deleterious matter, dressing of sides and bottom, filling back the excavated earth to the extent required and utilising /transporting the remaining earth upto 1.00km lead. including cost of labour, materials and HOM of machineries etc., complete.	Cum	56.88	84.00	Rupees Eighty Four Only
	Above 125%	Cum	1318.13	75.73	Rupees Seventy Five and Seventy Three Pais Only
9	KSRB 3.2: Providing and injecting chemical emulsion for Pre-constructional Anti-Termite Treatment, creating continuous chemical barrier under and around the column pits, walls, trenches, basement excavation, top surface of the plinth filling, junction of wall and floor,along the external perimeter of building,expansion joints,over the top surface of consolidated earth on which apron is to be laid,surrounding of pipes and conduits with chloropyriphos emulsifiable concentrates of 20% concentration,including cost of chemical,diluting in water to one percent concentration, labour, HOM of equipments, complete as per specifications.	Sqmt	475.00	128.00	Rupees One Hundred Twenty Eight Only
10	KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density. MORTH Specification No. 305	Cum	285.00	375.00	Rupees Three Hundred Seventy Five Only
11	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm & down size graded grinite metel coarse aggregates @ 0.892 cum & fine aggregates @ 0.465 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15cms, thick well compacted, in foundation & plinth, cost of all materials, labour, HOM of machinery, curing complete as per specification.	Cum	158.00	6264.00	Rupees Six Thousand Two Hundred Sixty Four Only
12	Providing and laying in position plain cement concrete of mix 1:2:4 with OPC cement @ 240kgs, with 20mm & down size graded grinite metel coarse aggregates @ 0.69 cum & fine aggregates @ 0.459 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15cms, thick well compacted, in foundation & plinth & Cills including cost of all materials, labour, HOM of machinery, curing complete as per specification.	Cum	54.50	6755.00	Rupees Six Thousand Seven Hundred Fifty Five Only
13	Providing & laying IN POSITION REINFORCED CEMENT CONCRETE of design mix M25 with OPC cement @ 340 Kgs with down size graded grinite metel coarse aggregates @ 0.70 Cum & fine aggregates @ 0.47 Cum with super plastisiser @ 3.0 Ltrs confirming to IS 9103-1999, re affirmed - 2008, Maichine mixed, concrete laid in layers not exeeceding 15cms thick, vibrated for all works in foundation ,Plinth,& Ground floor Level for Roof Slab, Staircase, Lintels, Retaining Wall, Pires, Abutments, Pillers, Posts, Struts, Butteress, String or Lasing Corsess, Prapeets Copings, Bed Blocks, anchor blocks, plain windows cills, filliets, etc including cost of all materials, laobur HOM of machinary, curing complete as per specification. - Ground Floor	Cum	42.50	7723.00	Rupees Seven Thousand Seven Hundred Twenty Three Only

Scanned with CamScanner

NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
14	Providing & laying IN POSITION REINFORCED CEMENT CONCRETE of design mix M25 with OPC cement @ 340 Kgs with down size graded grinite metel coarse aggregates @ 0.70 Cum & fine aggregates @ 0.47 Cum with super plastisiser @ 3.0 Ltrs confirming to IS 9103-1999, re affirmed - 2008, Maichine mixed, concrete laid in layers not exeeceding 15cms thick, vibrated for all works in foundation ,Plinth,& Ground floor Level for Roof Slab, Staircase, Lintels, Retaining Wall, Pires, Abutments, Pillers, Posts, Struts, Butteress, String or Lasing Corsess, Prapeets Copings, Bed Blocks, anchor blocks, plain windows cills, filliets, etc including cost of all materials, laobur HOM of machinary, curing complete as per specification. - First Floor	Cum	9.70	7785.00	Rupees Seven Thousand Seven Hundred Eighty Five Only
15	Providing & laying IN POSITION REINFORCED CEMENT CONCRETE of design mix M25 with OPC cement @ 340 Kgs with down size graded grinite metel coarse aggregates @ 0.70 Cum & fine aggregates @ 0.47 Cum with super plastisiser @ 3.0 Ltrs confirming to IS 9103-1999, re affirmed - 2008, Maichine mixed, concrete laid in layers not execeeding 15cms thick, vibrated for all works in foundation ,Plinth,& Ground floor Level for Roof Slab, Staircase, Lintels, Retaining Wall, Pires, Abutments, Pillers, Posts, Struts, Butteress, String or Lasing Corsess, Prapeets Copings, Bed Blocks, anchor blocks, plain windows cills, filliets, etc including cost of all materials, laobur HOM of machinary, curing complete as per specification. - Second Floor	Cum	7.38	7847.00	Rupees Seven Thousand Eight Hundred Forty Seven Only
	Above 125%	Cum	2.33	7522.70	Rupees Seven Thousand Five Hundred Twenty Two and Seventy Paise Only
16	Providing & laying IN POSITION REINFORCED CEMENT CONCRETE of design mix M25 with OPC cement @ 340 Kgs with down size graded grinite metel coarse aggregates @ 0.70 Cum & fine aggregates @ 0.47 Cum with super plastisiser @ 3.0 Ltrs confirming to IS 9103-1999, re affirmed - 2008, Maichine mixed, concrete laid in layers not execeeding 15cms thick, vibrated for all works in foundation ,Plinth,& Ground floor Level for Roof Slab, Staircase, Lintels, Retaining Wall, Pires, Abutments, Pillers, Posts, Struts, Butteress, String or Lasing Corsess, Prapeets Copings, Bed Blocks, anchor blocks, plain windows cills, filliets, etc including cost of all materials, laobur HOM of machinary, curing complete as per specification. - Third Floor	Cum	7.38	7909.00	Rupees Seven Thousand Nine Hundred Nine Only
	Above 125%	Cum	2.33	7597.19	Rupees Seven Thousand Five Hundred Ninety Seven and Nineteen Paise Only
17	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - Ground Floor	Cum	325.54	7750.00	Rupees Seven Thousand Seven Hundred Fifty Only
	Above 125%	Cum	273.86	6949.69	Rupees Six Thousand Nine Hundred Forty Nine and Sixty Nine Paise Only

Contractor

Executive Engineer(P)

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
18	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - First Floor	Cum	141.30	7750.00	Rupees Seven Thousand Seven Hundred Fifty Only
19	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - Second Floor	Cum	141.30	7750.00	Rupees Seven Thousand Seven Hundred Fifty Only
20	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - Third Floor	Cum	150.30	7750.00	Rupees Seven Thousand Seven Hundred Fifty Only
21	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - Terrace Floor	Cum	12.48	7750.00	Rupees Seven Thousand Seven Hundred Fifty Only
	Above 125%	Cum	5.03	7247.64	Rupees Seven Thousand Two Hundred Forty Seven and Sixty Four Paise Only
22	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for Foundation , footing , bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2	Sqm	341.60	287.00	Rupees Two Hundred Eighty Seven Only
23	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of beams, beam hauncing cantilever girders, bressumers & lintels & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications - Ground Floor	Sqm	955.10	318.00	Rupees Three Hundred Eighteen Only
24	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of beams, beam hauncing cantilever girders, bressumers & lintels & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications - First Floor	Sqm	445.90	324.00	Rupees Three Hundred Twenty Four Only
25	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of beams, beam hauncing cantilever girders, bressumers & lintels & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications - Second Floor	Sqm	430.63	330.00	Rupees Three Hundred Thirty Only
	Above 125%	Sqm	15.28	377.40	Rupees Three Hundred Seventy Seven and Forty Paise Only
26	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of beams, beam hauncing cantilever girders, bressumers & lintels & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications - Third Floor	Sqm	430.63	336.00	Rupees Three Hundred Thirty Six Only

Contractor

Executive Engineer(P)

Executive Engineer(P)

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
	Above 125%	Sqm	15.28	384.85	Rupees Three Hundred Eighty Four and Eighty Five Paise Only
27	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of beams, beam hauncing cantilever girders, bressumers & lintels & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications - Terrace Floor	Sqm	24.90	343.00	Rupees Three Hundred Forty Three Only
28	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. - Ground Floor	Sqm	337.00	454.00	Rupees Four Hundred Fifty Four Only
29	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. - First Floor	Sqm	148.40	461.00	Rupees Four Hundred Sixty One Only
30	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. - Second floor	Sqm	148.40	467.00	Rupees Four Hundred Sixty Seven Only
31	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. - Second floor	Sqm	148.40	473.00	Rupees Four Hundred Seventy Three Only
32	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. - Terrace floor	Sqm	15.10	479.00	Rupees Four Hundred Seventy Nine Only
33	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification upto 3.5 m from Ground level - Ground Floor	Sqm	740.13	683.00	Rupees Six Hundred Eighty Three Only
	Above 125%	Sqm	223.18	496.58	Rupees Four Hundred Ninety Six and Fifty Eight Paise Only
34	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification upto 3.5 m from Ground level - First Floor	Sqm	507.90	683.00	Rupees Six Hundred Eighty Three Only
35	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification upto 3.5 m from Ground level - Second Floor	Sqm	507.90	683.00	Rupees Six Hundred Eighty Three Only
36	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification upto 3.5 m from Ground level - Third Floor	Sqm	530.42	683.00	Rupees Six Hundred Eighty Three Only

Executive Engineer

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
37	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification upto 3.5 m from Ground level - Terrace Floor	Sqm	43.38	683.00	Rupees Six Hundred Eighty Three Only
	Above 125%	Sqm	10.63	496.58	Rupees Four Hundred Ninety Six and Fifty Eight Paise Only
38	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications - Ground Floor	Sqm	52.80	842.00	Rupees Eight Hundred Forty Two Only
39	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications - First Floor	Sqm	26.70	848.00	Rupees Eight Hundred Forty Eight Only
40	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications - Second Floor	Sqm	26.70	854.00	Rupees Eight Hundred Fifty Four Only
41	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications - Third Floor	Sqm	26.70	860.00	Rupees Eight Hundred Sixty Only
42	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications - Terrace Floor	Sqm	3.38	867.00	Rupees Eight Hundred Sixty Seven Only
	Above 125%	Sqm	0.23	937.30	Rupees Nine Hundred Thirty Seven and Thirty Paise Only
43	Providing and removing centring, shuttering, strutting, proping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials,labour complete as per specification and directed by the Engineer in Charge. Ground Floor	Sqm	35.63	590.00	Rupees Five Hundred Ninety Only
	Above 125%	Sqm	25.58	645.56	Rupees Six Hundred Forty Five and Fifty Six Paise Only
44	Providing and removing centring, shuttering, strutting, proping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials,labour complete as per specification and directed by the Engineer in Charge. First Floor	Sqm	32.40	596.00	Rupees Five Hundred Ninety Six Only
45	Providing and removing centring, shuttering, strutting, proping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials,labour complete as per specification and directed by the Engineer in Charge. Second Floor	Sqm	28.50	602.00	Rupees Six Hundred Two Only
	Above 125%	Sqm	3.90	645.56	Rupees Six Hundred Forty Five and Fifty Six Paise Only
46	Providing and removing centring, shuttering, strutting, proping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials,labour complete as per specification and directed by the Engineer in Charge. Third Floor	Sqm	28.50	608.00	Rupees Six Hundred Eight Only
	Above 125%	Sqm	3.90	645.56	Rupees Six Hundred Forty Five and Fifty Six Paise Only

Contractor

Executive Engineer(P)

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
37	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification upto 3.5 m from Ground level - Terrace Floor	Sqm	43.38	683.00	Rupees Six Hundred Eighty Three Only
	Above 125%	Sqm	10.63	496.58	Rupees Four Hundred Ninety Six and Fifty Eight Paise Only
38	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications - Ground Floor	Sqm	52.80	842.00	Rupees Eight Hundred Forty Two Only
39	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications - First Floor	Sqm	26.70	848.00	Rupees Eight Hundred Forty Eight Only
40	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications - Second Floor	Sqm	26.70	854.00	Rupees Eight Hundred Fifty Four Only
41	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications - Third Floor	Sqm	26.70	860.00	Rupees Eight Hundred Sixty Only
42	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications - Terrace Floor	Sqm	3.38	867.00	Rupees Eight Hundred Sixty Seven Only
	Above 125%	Sqm	0.23	937.30	Rupees Nine Hundred Thirty Seven and Thirty Paise Only
43	Providing and removing centring, shuttering, strutting, proping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials,labour complete as per specification and directed by the Engineer in Charge. Ground Floor	Sqm	35.63	590.00	Rupees Five Hundred Ninety Only
	Above 125%	Sqm	25.58	645.56	Rupees Six Hundred Forty Five and Fifty Six Paise Only
44	Providing and removing centring, shuttering, strutting, proping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials,labour complete as per specification and directed by the Engineer in Charge. First Floor	Sqm	32.40	596.00	Rupees Five Hundred Ninety Six Only
45	Providing and removing centring, shuttering, strutting, proping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials,labour complete as per specification and directed by the Engineer in Charge. Second Floor	Sqm	28.50	602.00	Rupees Six Hundred Two Only
	Above 125%	Sqm	3.90	645.56	Rupees Six Hundred Forty Five and Fifty Six Paise Only
46	Providing and removing centring, shuttering, strutting, proping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials,labour complete as per specification and directed by the Engineer in Charge. Third Floor	Sqm	28.50	608.00	Rupees Six Hundred Eight Only
	Above 125%	Sqm	3.90	645.56	Rupees Six Hundred Forty Five and Fifty Six Paise Only

Contractor

Executive Engineer(P)

Scanned with CamScanner

NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
47	Providing and laying in position reinforced cement cocnrete of design mix M20 with OPC cement @ 27.20 Kgs with 12mm & down sizes graded grantie metal coarse aggregated @ 0.5865 cum & fine aggregates, @ 0.391 Cum with super super plastisiser @ 0.225 Ltrs maichine mixed well compacted plain chajja 7.50 Cms avg thickness, up to ground floor level including removing centering, shuttering, strutting, propping etc., and removal of form work for cost of all materials, laobur HOM of machinary, curing complete as per specification. Ground Floor	Sqm	27.50	566.00	Rupees Five Hundred Sixty Six Only
48	Providing and laying in position reinforced cement cocnrete of design mix M20 with OPC cement @ 27.20 Kgs with 12mm & down sizes graded grantie metal coarse aggregated @ 0.5865 cum & fine aggregates, @ 0.391 Cum with super super plastisiser @ 0.225 Ltrs maichine mixed well compacted plain chajja 7.50 Cms avg thickness, up to ground floor level including removing centering, shuttering, strutting, propping etc., and removal of form work for cost of all materials, laobur HOM of machinary, curing complete as per specification. First Floor	Sqm	18.90	572.00	Rupees Five Hundred Seventy Two Only
49	Providing and laying in position reinforced cement cocnrete of design mix M20 with OPC cement @ 27.20 Kgs with 12mm & down sizes graded grantie metal coarse aggregated @ 0.5865 cum & fine aggregates, @ 0.391 Cum with super super plastisiser @ 0.225 Ltrs maichine mixed well compacted plain chajja 7.50 Cms avg thickness, up to ground floor level including removing centering, shuttering, strutting, propping etc., and removal of form work for cost of all materials, laobur HOM of machinary, curing complete as per specification. Second Floor	Sqm	18.90	579.00	Rupees Five Hundred Seventy Nine Only
50	Providing and laying in position reinforced cement cocnrete of design mix M20 with OPC cement @ 27.20 Kgs with 12mm & down sizes graded grantie metal coarse aggregated @ 0.5865 cum & fine aggregates, @ 0.391 Cum with super super plastisiser @ 0.225 Ltrs maichine mixed well compacted plain chajja 7.50 Cms avg thickness, up to ground floor level including removing centering, shuttering, strutting, propping etc., and removal of form work for cost of all materials, laobur HOM of machinary, curing complete as per specification. Third Floor	Sqm	18.90	585.00	Rupees Five Hundred Eighty Five Only
51	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels of all shapes & sizes, at all elevations & heights. Ground Floor	Sqm	28.00	335.00	Rupees Three Hundred Thirty Five Only
52	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels of all shapes & sizes, at all elevations & heights. First Floor	Sqm	19.00	341.00	Rupees Three Hundred Forty One Only
53	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels of all shapes & sizes, at all elevations & heights. Second Floor	Sqm	19.00	348.00	Rupees Three Hundred Forty Eight Only
54	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels of all shapes & sizes, at all elevations & heights. Third Floor	Sqm	19.00	354.00	Rupees Three Hundred Fifty Four Only
55	Extra For providing throating or drip moulding to RCC chajjas with plastreing(labour charges only), as perspecification - Ground Floor	Rmtr	75.00	25.00	Rupees Twenty Five Only
56	Extra For providing throating or drip moulding to RCC chajjas with plastreing(labour charges only), as perspecification - First Floor	Rmtr	30.00	25.00	Rupees Twenty Five Only
57	Extra For providing throating or drip moulding to RCC chajjas with plastreing(labour charges only), as perspecification - Second Floor	Rmtr	30.00	25.00	Rupees Twenty Five Only

Contractor

Executive Engineer(P)

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
58	Extra For providing throating or drip moulding to RCC chajjas with plastreing(labour charges only), as perspecification - Third Floor	Rmtr	30.00	25.00	Rupees Twenty Five Only
59	Providing lath plastering cement mortor 1:3, 5 Cm thick with 6 mm dia mild steel @ 20 cm c/c both hiorizantaly & Vertically fixing Chicken Mesh for drop chejja , facia, Backing to cupboard including cost of all materials, labour, providing & removing form work H O M of Machinery , curing, complete as per specifications.	Sqm	113.00	1200.00	Rupees One Thousand Two Hundred Only
60	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 - Ground Floor	MT	62.50	75241.00	Rupees Seventy Five Thousand Two Hundred Forty One Only
	Above 125%	MT	11.00	88101.45	Rupees Eighty Eight Thousand One Hundred One and Forty Five Paise Only
61	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 - First Floor	MT	21.10	75827.00	Rupees Seventy Five Thousand Eight Hundred Twenty Seven Only
62	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 - Second floor	MT	21.10	76413.00	Rupees Seventy Six Thousand Four Hundred Thirteen Only
63	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 - Third Floor	MT	21.10	76999.00	Rupees Seventy Six Thousand Nine Hundred Ninety Nine Only
64	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 - Terrace Floor	MT	1.79	77585.00	Rupees Seventy Seven Thousand Five Hundred Eighty Five Only

Contractor

Executive Engineer(P)

Scanned with CamScanner

Sl. NO	Description of Item	Unit	Qty	Rate in	
				Figures	Words
1	2	3	4	5	6
58	Extra For providing throating or drip moulding to RCC chajjas with plastreing(labour charges only), as perspecification - Third Floor	Rmtr	30.00	25.00	Rupees Twenty Five Only
59	Providing lath plastering cement mortor 1:3, 5 Cm thick with 6 mm dia mild steel @ 20 cm c/c both hiorizantaly & Vertically fixing Chicken Mesh for drop chejja , facia, Backing to cupboard including cost of all materials, labour, providing & removing form work H O M of Machinery , curing, complete as per specifications.	Sqm	113.00	1200.00	Rupees One Thousand Two Hundred Only
60	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 - Ground Floor	MT	62.50	75241.00	Rupees Seventy Five Thousand Two Hundred Forty One Only
	Above 125%	MT	11.00	88101.45	Rupees Eighty Eight Thousand One Hundred One and Forty Five Paise Only
61	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 - First Floor	MT	21.10	75827.00	Rupees Seventy Five Thousand Eight Hundred Twenty Seven Only
62	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 - Second floor	MT	21.10	76413.00	Rupees Seventy Six Thousand Four Hundred Thirteen Only
63	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 - Third Floor	MT	21.10	76999.00	Rupees Seventy Six Thousand Nine Hundred Ninety Nine Only
64	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 - Terrace Floor	MT	1.79	77585.00	Rupees Seventy Seven Thousand Five Hundred Eighty Five Only

Contractor

Executive Engineer(P)

Scanned with CamScanner